Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVENT IS CODES FOR EARTH QUAKE RESISTANCE.
2. THE BUILDING IS ARTIFICALLY LIT AND MECHANICALLY VENTILATED.

LEGEND:-

PROJECT : THE ARBOUR

REVISED (2nd Revision) BUILDING PLANS OF GROUP HOUSING COLONY AREA MEASURING 25.087 ACRES (LICENCE NO. 123 OF 2012 DATED 20-12-2012 IN SECTOR-63, GURGAON BEING DEVELOPED BY ARLIE BUILDERS & DEVELOPERS PVT. LTD. AND OTHERS IN COLLABORATION WITH DLF HOME DEVELOPERS LTD(EARLIER KNOWN AS DLF NEW GURGAON HOME DEVELOPERS PVT.LTD)

ARCHITECTURE:
ARCOP
ARCOP ASSOCIATES PVT LTD
Plot No. 36B, Sector-32, Intitutional Area,
Gurugram. Haryana. 122001. India
Tel.: 91-124-4595500
91-124-4595550
Fax: 91-124-4595555

ASSOCIATE ARCHITECTS
RSMS ARCHITECTS
RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi-110070.
Tel.: 011-26898616,26898617
www.rsms-arch.com

DOOR SCHEDULE

S.NO.	TYPE	ROUGH OPENING	CLEAR OPENING	SILL HT	LINTEL HT	FIRE RATING	DOOR LEAF	MATERIAL OF FRAME	MATERIAL OF SHUTTERS
1	FD2	1250 X 2100	1104 X 2027	_	2100	2 HR.	SINGLE	AS SPECIFIED	AS SPECIFIED
2	FD3	1050 X 2473	904 X 2400	100	2573	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
3	FD4	1050 X 2473	904 X 2400	100	2573	2 HR.	SINGLE	AS SPECIFIED	AS SPECIFIED
4	FD5	1350 X 2173	1204 X 2100	100	2273	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
5	FD6	1050 X 2173	904 X 2100	100	2273	2 HR.	SINGLE	AS SPECIFIED	AS SPECIFIED
6	FD7	1400 X 2173	1254 X 2100	100	2273	2 HR.	SINGLE	AS SPECIFIED	AS SPECIFIED
7	FD8	1350 X 2173	1204 X 2100	100	2273	2 HR.	SINGLE	AS SPECIFIED	AS SPECIFIED
8	FD9	2150 X 2500	2004 X 2427	_	2600	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
9	FD10	2550 X 3073	2404 X 3000	_	3173	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
10	FD11	2550 X 3073	2404 X 3000	_	3173	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
11	FD12	2550 X 3073	2404 X 3000	_	3173	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
12	FD13	2560 X 3073	2404 X 3000	_	3173	2 HR.	DOUBLE	AS SPECIFIED	AS SPECIFIED
13	RS	_	4000 X 4000	_	_	2 HR.	ROLLING SHUTTER	AS SPECIFIED	AS SPECIFIED

*TD= TRAVEL DISTANCE

SCHEDULE OF OPENINGS ON TYPICAL/BASEMENT FLOOR

S.No	TYPE	ROUGH OPENING WIDTH	ROUGH OPENING HEIGHT	FINISHED OPENING WIDTH	FINISHED OPENING HEIGHT	SILL HT	LINTEL HT	FIRE RATING
1.	D	1050	2100	1020	2085	–	2100	–
2.	D1	800	2400	770	2385	–	2400	–
3.	D2	900	2400	870	2385	–	2400	–
4.	D3	1050	2400	1020	2385	–	2400	–
5.	D4	600	2100	570	2085	100	2100	–
6.	D5	600	1500	570	1485	900	2400	–
7.	D6	800	2100	770	2085	–	2100	–
8.	D7	1200	2400	1170	2385	–	2400	–

CAR PARKING = 490
WASH CAR PARKING = 10
TOTAL CAR PARKING = 480

SOUTH POCKET
BASEMENT -01
LVL-4850

LEGEND :-

	①	160Ø uPVC SOIL O/T PIPE
	②	160Ø uPVC WASTE O/T PIPE
	③	110Ø uPVC ANTI-PHYTHONE PIPE
	④	160Ø uPVC SOIL/O/T PIPE
	⑤	160Ø uPVC RAIN WATER DOWNTAKE PIPE
	⑥	DOMESTIC WATER SUPPLY DOWNTAKE PIPE
	⑦	FLUSHING WATER SUPPLY DOWNTAKE PIPE
	⑧	110Ø uPVC BALCONY DRAIN PIPE
	⑨	HOT WATER SUPPLY DOWNTAKE PIPE FROM SOLAR
	COP	CLEAN OUT PLUG
	N.T.	NAHANI TRAP
	M.N.T.	MULTI NAHANI TRAP
		BASIN OUTLET
	F.T.	FLOOR TRAP
	P1	400x400MM CUTOUT IN FLOOR
	1	Ø150MM SLEEVE FOR B1&B2 FLOOR
	2	Ø150MM SLEEVE FOR B1&B2 FLOOR
		DOTTED LINE TYPE SHOWS FOR CEILING OPENING (TYP.)
		HATCH AREA SHOWS FOR FLOOR OPENING (TYP.)
		CONTINUOUS LINE TYPE SHOWS FOR FLOOR OPENING (TYP.)
	E.PANEL	ELECTRICAL PANEL (E.P.) FOR DRAINAGE & SEWAGE SUMP

Checked and found ok for Public Health (Nilmab) Service only subject to comments in forwarding letter No 2045 Dt 28/5/2014
Superintending Engineer (HQ)
for Chief Engineer-I
HSVP, Panchkula

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting objections from the general public

A.T.P. (HQ) Member B.P.A.C.	S.T.P. (HQ) Member Secretary B.P.A.C.	S.T.P. (G) Member B.P.A.C.	C.T.P. (HK) Chairman B.P.A.C.

DDT (T) MEMBER BPAC

ATP(HQ)

P.A.

S.T.P.

DINESH KUMAR PAHUJA

S.D.

TO BE READ WITH THIS OFFICE MEMO NO.: DATED :

ARCHITECT'S SEAL & SIGNATURE	OWNER'S SEAL & SIGNATURE
	DLF Home Developers Limited Authorised Signatory

MARCH 2014 | Scale : 1:200

Drawing Title:-
BASEMENT-01(SOUTH POCKET) PLUMBING PLAN UNDER TOWER-D,E

Drawing No:-
BS-04A