GROUND FLOOR (CARPET AREA) BLOCK – J								
G1	=	1	X	3.500	X	9.385	=	32.855 SQM
G1a	=	1	X	2.540	X	0.750	=	1.909 SQM
G2	=	1	X	3.500	X	10.739	=	37.171 SQM
G3	=	1	X	3.050	X	10.735	=	33.171 SQM
G4	=	1	X	3.050	X	10.735	=	32.302 SQM
G5	=	1	X	3.450	X	9.995	=	34.483 SQM
G6	=	1	X	3.500	X	9.385	=	32.855 SQM
G7	=	1	X	3.585	X	10.739	=	38.338 SQM
G8	=	1	X	3.475	X	9.830	=	34.125 SQM
G9a	=	1	X	1.200	X	0.913	=	1.095 SQM
G9	=	1	X	3.470	X	9.830	=	33.777 SQM
G9b	=	1	X	3.470	X	0.830	=	2.880 SQM
G9c	=	1	X	4.130	X	2.150	=	8.882 SQM
						TOTAL	=	359.866 SQM

GROUND FLOOR (CARPET AREA) BLOCK – H								
G1	=	1	X	3.565	X	9.385	=	31.466 SQM
G1a	=	1	X	2.540	X	0.550	=	1.331 SQM
G1b	=	1	X	3.475	X	1.400	=	3.665 SQM
G2	=	1	X	3.610	X	9.773	=	34.169 SQM
G3	=	1	X	3.535	X	9.995	=	35.330 SQM
G4	=	1	X	3.535	X	10.000	=	34.406 SQM
G4	=	1	X	3.535	X	10.739	=	34.406 SQM
G5	=	1	X	3.556	X	10.735	=	34.406 SQM
G6	=	1	X	3.790	X	9.735	=	37.220 SQM
G7	=	1	X	3.655	X	9.735	=	33.156 SQM
						TOTAL	=	331.162 SQM

GROUND FLOOR (CARPET AREA) BLOCK –G								
G1	=	1	X	3.620	X	9.610	=	34.791 SQM
G1a	=	1	X	4.360	X	4.465	=	19.313 SQM
G2	=	1	X	8.895	X	3.855	=	33.292 SQM
G3	=	1	X	3.505	X	1.920	=	6.729 SQM
G3	=	1	X	9.990	X	3.905	=	38.990 SQM
G4	=	1	X	3.515	X	11.315	=	39.769 SQM
G4	=	1	X	3.505	X	0.990	=	3.470 SQM
G5	=	1	X	3.505	X	10.735	=	37.630 SQM
G6	=	1	X	4.585	X	3.695	=	16.941 SQM
G6	=	1	X	3.410	X	11.315	=	61.214 SQM
						TOTAL	=	331.998 SQM

GROUND FLOOR (CARPET AREA) BLOCK-F								
G1	=	1	X	1.150	X	7.815	=	8.987 SQM
G1a	=	1	X	4.410	X	7.815	=	19.208 SQM
G2	=	1	X	4.410	X	7.815	=	19.208 SQM
G3	=	1	X	3.600	X	0.795	=	2.862 SQM
G3a	=	1	X	3.600	X	0.795	=	2.570 SQM
G4	=	1	X	4.480	X	7.815	=	37.736 SQM
G4	=	1	X	3.600	X	0.550	=	21.168 SQM
G4a	=	1	X	3.115	X	4.425	=	8.935 SQM
G4b	=	1	X	1.520	X	7.815	=	11.990 SQM
G5	=	1	X	4.305	X	4.425	=	9.873 SQM
						TOTAL	=	131.971 SQM

GROUND FLOOR (CARPET AREA) BLOCK -E								
G1	=	1	X	4.585	X	9.995	=	33.481 SQM
G2	=	1	X	4.485	X	3.705	=	19.855 SQM
G3	=	1	X	1.365	X	9.995	=	36.153 SQM
G4	=	1	X	1.400	X	9.995	=	31.615 SQM
G5	=	1	X	1.400	X	9.995	=	31.615 SQM
G5a	=	1	X	3.600	X	4.455	=	7.569 SQM
G6	=	1	X	4.235	X	5.550	=	22.835 SQM
G7	=	1	X	1.310	X	5.550	=	12.459 SQM
G8	=	1	X	1.345	X	3.405	=	25.512 SQM
G9	=	1	X	1.345	X	3.405	=	27.202 SQM
G9a	=	1	X	0.835	X	4.455	=	3.645 SQM
G9b	=	1	X	1.310	X	4.455	=	5.835 SQM
G9c	=	1	X	1.305	X	4.550	=	16.981 SQM
G9d	=	1	X	3.930	X	0.775	=	2.340 SQM
G10	=	1	X	3.515	X	5.550	=	56.822 SQM
G11	=	1	X	3.690	X	3.940	=	22.207 SQM
G12	=	1	X	3.690	X	3.940	=	22.207 SQM
G13	=	1	X	4.455	X	3.955	=	31.734 SQM
						TOTAL	=	497.603 SQM

GROUND FLOOR (CARPET AREA) BLOCK-C								
G1	=	1	X	4.315	X	4.650	=	22.615 SQM
G2	=	1	X	3.555	X	5.570	=	50.068 SQM
G2a	=	1	X	4.880	X	0.950	=	4.636 SQM
G2b	=	1	X	4.880	X	0.450	=	2.196 SQM
G3	=	1	X	3.520	X	4.475	=	15.752 SQM
G4	=	1	X	3.555	X	4.475	=	15.909 SQM
G5	=	1	X	1.240	X	4.475	=	12.632 SQM
G6	=	1	X	19.750	X	5.550	=	69.750 SQM
G7	=	1	X	13.070	X	5.550	=	17.473 SQM
G7a	=	1	X	0.690	X	1.710	=	1.180 SQM
G7b	=	1	X	0.690	X	1.710	=	1.180 SQM
G7c	=	1	X	0.690	X	2.060	=	1.418 SQM
G7d	=	1	X	5.780	X	0.900	=	3.780 SQM
G8	=	1	X	5.665	X	7.645	=	39.283 SQM
G8a	=	1	X	1.500	X	0.710	=	1.065 SQM
G8b	=	1	X	0.500	X	5.665	=	2.833 SQM
G9	=	1	X	3.470	X	4.650	=	16.985 SQM
G9a	=	1	X	3.470	X	0.950	=	3.433 SQM
G9b	=	1	X	3.470	X	2.880	=	9.994 SQM
G9c	=	1	X	4.130	X	2.150	=	8.882 SQM
G10a	=	1	X	1.370	X	0.760	=	0.774 SQM
G10b	=	1	X	1.265	X	0.565	=	0.713 SQM
G11	=	1	X	4.935	X	11.525	=	56.870 SQM
G11a	=	1	X	0.975	X	2.995	=	2.921 SQM
G11b	=	1	X	0.975	X	7.460	=	6.895 SQM
G12	=	1	X	5.180	X	7.300	=	37.668 SQM
G13	=	1	X	5.180	X	4.130	=	21.393 SQM
G14	=	1	X	6.185	X	4.495	=	27.802 SQM
G14a	=	1	X	4.200	X	3.515	=	13.482 SQM
G14b	=	1	X	0.615	X	1.100	=	0.730 SQM
G14c	=	1	X	3.420	X	1.230	=	4.207 SQM
						TOTAL	=	506.305 SQM

GROUND FLOOR (CARPET AREA) BLOCK-G								
G1	=	1	X	6.240	X	7.675	=	47.892 SQM
G1a	=	1	X	6.240	X	4.000	=	24.960 SQM
G2	=	1	X	5.515	X	11.415	=	62.950 SQM
G3	=	1	X	5.515	X	11.415	=	62.950 SQM
G3	=	1	X	5.145	X	13.125	=	67.513 SQM
G4	=	1	X	5.145	X	12.525	=	63.412 SQM
G5	=	1	X	6.955	X	3.500	=	24.343 SQM
G5	=	1	X	5.550	X	4.115	=	22.838 SQM
G6	=	1	X	5.550	X	4.115	=	22.838 SQM
G7	=	1	X	5.550	X	4.050	=	22.478 SQM
G9	=	1	X	5.715	X	4.650	=	26.582 SQM
G9a	=	1	X	1.730	X	4.155	=	7.654 SQM
G9b	=	1	X	1.155	X	0.650	=	0.713 SQM
G9c	=	1	X	1.155	X	0.650	=	0.713 SQM
G10	=	1	X	10.160	X	7.560	=	44.467 SQM
G10a	=	1	X	0.815	X	5.435	=	2.809 SQM
G10b	=	1	X	0.815	X	5.575	=	2.914 SQM
G11	=	1	X	5.145	X	15.960	=	82.350 SQM
G12	=	1	X	5.715	X	15.960	=	90.530 SQM
G12a	=	1	X	1.350	X	11.515	=	19.478 SQM
G12b	=	1	X	1.350	X	11.515	=	19.478 SQM
G13	=	1	X	5.715	X	15.960	=	86.150 SQM
G14	=	1	X	6.240	X	15.960	=	99.178 SQM
G15	=	1	X	4.790	X	4.835	=	22.670 SQM
G16	=	1	X	5.715	X	5.575	=	30.900 SQM
G17	=	1	X	5.715	X	5.575	=	30.900 SQM
G17a	=	1	X	1.215	X	1.860	=	2.260 SQM
G17b	=	1	X	1.200	X	2.405	=	4.680 SQM
						TOTAL	=	859.319 SQM

GROUND FLOOR (CARPET AREA) BLOCK-B								
G1	=	1	X	4.405	X	8.195	=	36.090 SQM
G1a	=	1	X	3.810	X	2.470	=	9.411 SQM
G1b	=	1	X	3.805	X	2.470	=	9.399 SQM
G2	=	1	X	4.960	X	8.520	=	42.259 SQM
G3	=	1	X	4.960	X	8.520	=	34.117 SQM
G4	=	1	X	3.775	X	9.000	=	34.100 SQM
G5	=	1	X	3.830	X	9.060	=	35.420 SQM
G6	=	1	X	11.615	X	5.000	=	61.750 SQM
G7	=	1	X	11.615	X	6.645	=	77.124 SQM
G8	=	1	X	3.805	X	8.520	=	32.410 SQM
G9	=	1	X	3.965	X	8.520	=	31.720 SQM
G10	=	1	X	3.830	X	2.625	=	9.316 SQM
G10a	=	1	X	4.665	X	0.580	=	1.926 SQM
G10b	=	1	X	3.810	X	5.140	=	19.009 SQM
G10c	=	1	X	3.805	X	5.140	=	19.009 SQM
G10d	=	1	X	3.830	X	6.000	=	9.180 SQM
G10e	=	0.5	X	0.710	X	0.670	=	0.096 SQM
G10f	=	1	X	0.710	X	0.530	=	0.204 SQM
G10g	=	1	X	2.700	X	0.700	=	1.890 SQM
G10h	=	1	X	3.255	X	0.700	=	2.278 SQM
G11	=	1	X	4.960	X	8.520	=	40.580 SQM
G12	=	1	X	4.810	X	8.150	=	41.032 SQM
G12a	=	1	X	1.555	X	1.720	=	5.512 SQM
G12b	=	1	X	0.535	X	1.140	=	0.599 SQM
G12c	=	1	X	0.535	X	0.810	=	0.709 SQM
G13	=	1	X	5.975	X	6.645	=	69.224 SQM
G14	=	1	X	5.975	X	6.645	=	69.587 SQM
						TOTAL	=	638.397 SQM

GROUND FLOOR (CARPET AREA) BLOCK – A								
G1	=	1	X	4.515	X	4.020	=	18.150 SQM
G1a	=	1	X	9.505	X	4.955	=	47.097 SQM
G2	=	1	X	3.905	X	7.995	=	31.185 SQM
G3	=	1	X	3.965	X	7.965	=	31.109 SQM
G4	=	1	X	3.975	X	7.965	=	31.663 SQM
G5	=	1	X	3.955	X	7.965	=	31.504 SQM
G6	=	1	X	3.955	X	4.955	=	19.352 SQM
G6a	=	1	X	1.055	X	4.570	=	5.212 SQM
G6b	=	1	X	0.795	X	3.960	=	3.094 SQM
G7	=	1	X	3.955	X	4.550	=	17.990 SQM
G8	=	1	X	6.195	X	4.430	=	28.082 SQM
G9	=	1	X	6.195	X	4.430	=	28.082 SQM
G10	=	1	X	3.455	X	6.715	=	16.141 SQM
G10a	=	1	X	6.195	X	3.910	=	12.972 SQM
G10b	=	1	X	1.455	X	0.560	=	1.706 SQM
G11	=	1	X	3.415	X	6.715	=	22.681 SQM
G12	=	1	X	3.415	X	13.945	=	47.626 SQM
G13	=	1	X	3.755	X	13.945	=	48.730 SQM
G13a	=	1	X	1.015	X	0.840	=	0.853 SQM
G14	=	1	X	3.815	X	13.945	=	50.702 SQM
G15	=	1	X	3.934	X	10.805	=	41.629 SQM
G15a	=	1	X	1.455	X	1.420	=	2.066 SQM
G15b	=	1	X	3.635	X	0.840	=	3.053 SQM
G16	=	1	X	3.635	X	13.945	=	45.644 SQM
G17	=	1	X	3.635	X	13.945	=	45.644 SQM
G18	=	1	X	3.515	X	13.945	=	49.118 SQM
G18a	=	1	X	1.555	X	10.435	=	16.187 SQM
G18b	=	1	X	4.765	X	3.995	=	18.430 SQM
G18c	=	1	X	4.765	X	3.995	=	18.430 SQM
G18d	=	1	X	0.615	X	1.100	=	0.676 SQM
G18e	=	1	X	0.955	X	1.075	=	0.169 SQM
G18f	=	1	X	4.485	X	7.570	=	33.782 SQM
G18g	=	1	X	4.595	X	7.190	=	33.182 SQM
G18h	=	0.5	X	4.485	X	1.100	=	2.468 SQM
G18i	=	1	X	4.485	X	7.100	=	10.318 SQM
						TOTAL	=	793.443 SQM

TOTAL CARPET AREA OF GROUND FLOOR	=	GROSS-A	=	GROSS-B	=	GROSS-C	=	GROSS-D	=	GROSS-E	=	GROSS-F	=	GROSS-G	=	GROSS-H	=	GROSS-I
	=	793.443	=	638.397	=	859.319	=	506.306	=	497.603	=	131.971	=	335.998	=	331.162	=	359.866
TOTAL	=	4152.516 SQM																

GROUND FLOORFLOOR
CARPET AREAAREA

Note :-

1.BUILDING HAS AUTOMATIC SPRINKLER SYSTEM.

2. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

3. BUILDING IS ARTIFICIALLY LIGHTED MECHANICALLY VENTILATED AND AIR CONDITIONED WITH 100% POWER BACKUP.

4. ALL THE SHAFT WILL BE PROVIDED WITH GALVANIZED METAL GRATING FLUSH TO THE ROAD LEVEL TO TAKE FIRE TENDER LOAD.

PROJECT:
PROPOSED BUILDING PLAN OF (SUMMIT PLAZA) COMMERCIAL SITE UNDER TRANSIT ORIENNTED DEVELOPMENT (TOD) POLICY DATED 09.02.2016 ON THE AREA MEASURING 2.65 ACRES FALLING IN RESIDENTIAL CUM-GROUP HOUSING COLONY NAMELY DLF-5 (FORMERLY KNOWN AS DLF CITY PHASE-V), GURUGRAM BEING DEVELOPED BY DLF LIMITED.

ASSOCIATE ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi-110070.
Tel.: 011-26898616,26898617
www.rsms-arch.com

(STATE) Director Member BPC

(DTCP) Senior Planner BPC

(DTCP) Senior Planner BPC

(DTCP) Chief Planner BPC

Ram Avtar Bansal (ADMC)

(DDT-HQ) Member BPC

JD PA AP

ARCHITECT'S SEAL & SIGNATURE	OWNER'S SEAL & SIGNATURE

13 APRIL- 2021 | Scale :1:100

Drawing Title:-
GROUND FLOOR
CARPET AREA CALCULATION

Drawing No:-
CP-01