ZONE-1
2845 Sq.mt

ZONE-2
2730 Sq.mt

ZONE-3
2270 Sq.mt

ZONE-4
2460 Sq.mt

ZONE-5
2600 Sq.mt

ZONE-6
2800 Sq.mt

ZONE-7
2820Sq.mt

BASEMENT -1
LVL - 4830
TOTAL NORMAL CAR PARKING = 493
PART-2

SCHEDULE OF OPENINGS ON FLOOR

S.No	TYPE	WIDTH	HEIGHT	SILL HT.	PER FLOOR	FIRE RATING	MATERIAL	LOCATION
1.	D1	1050	2400	--		--	WOODEN	BASEMENT --1
2.	GLZ1	2125	2400	--		2 HRS FIRE RATED	ALUMINIUM /GLASS	BASEMENT --1
3.	GLZ2	5940	2400	--		2 HRS FIRE RATED	ALUMINIUM /GLASS	BASEMENT --1
4.	GLZ3	5740	2400	--		2 HRS FIRE RATED	ALUMINIUM /GLASS	BASEMENT --1
6.	S1	4000	4000	--		2 HRS FIRE RATED	ROLLING SHUTTER	BASEMENT--1
7.	FD	1050	2400	--		2 HRS FIRE RATED	AS SPECIFIED	BASEMENT --1
7.	FD1	1200	2400	--		2 HRS FIRE RATED	AS SPECIFIED	BASEMENT --1
8.	FD2	1250	2400	--		2 HRS FIRE RATED	AS SPECIFIED	FIRE TOWER SERVICES
9	FH1	1250	2400	--		2 HRS FIRE RATED	ALUMINIUM /GLASS	F.H.C
10	FH1	1500	2400	--		2 HRS FIRE RATED	AS SPECIFIED	TRANSFORMER
11.	FD5	2400	2400	--		2 HRS FIRE RATED		PHE PLANT ROOM FIRE PUMP ROOM
12.	FD6	3000	2400	--		2 HRS FIRE RATED		FIRE TOWER

PHE LEGENDS :

		300/450mm WIDE DRAIN CHANNEL (SLOPE 1: 300) TYPICAL
•	F.D.	FLOOR DRAIN
		ø110mm PARKING DRAIN PIPE (TYP.)
		RIDGE LINE
		SLOPE DIRECTION
		PARKING SURFACE SLOPE SHALL BE CONFIRMED BY ARCH. / DLF SINCE THIS HAVE IMPACT ON THE BASEMENT HEIGHT , SCREED THICKNESS & LOADING ON STRUCTURE
		DISTANCE BETWEEN RIDGE & DRAIN CONSIDERED IS AROUND 10 TO 20MTRS.

NO.	SLEEVES FOR SUMP
1.	2000X2000 MM MANHOLE COVER
2.	CI FOOT STEPS DETAIL (LOCATION CHANGE AS PER SITE INLET CONNECTION)
3.	30M3/HRS MUD PUMP WITH AUTO ON/OFF SWITCH AND LEVEL CONTROLLER (1W+1S)
4.	150X150MM CUT OUT FOR DISCHARGE PIPE IN SUMP TOP SLAB
5.	100MM/150 ø DISCHARGE PIPE
6.	75MM ø VENT PIPE
7.	100X100MM CUTOUT FOR VENT PIPE IN SUMP TOP SLAB
8.	50MM ø SLEEVE FOR ELECTRIC CABLE IN SUMP SIDE WALL (LOCATION AS PER SITE.)
9.	50 MM WATER PROOFING
10.	FLOAT SWITCH STEEL ANGLE SUPPORT
11.	ALARM LEVEL
12.	ASSIST PUMP START
13.	DUTY PUMP START
14.	DRY RUN PROTECTION
15.	PULL CHAIN AS/APPROVED MATERIAL
16.	300X300MM CUT OUT FOR INLET PIPE IN SUMP (LOCATION & I.L AS PER SITE.)
17.	200ø / 300ø / 450ø DRAIN INLET PIPE (LOCATION & I.L AS PER SITE.)

NOTE :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVENT IS CODES FOR EARTH QUAKE RESISTANCE.
2. THE BUILDING IS ARTIFICALLY LIT AND MECHANICALLY VENTILATED.

LEGEND:-

PROJECT :

REVISED BUILDING PLANS OF GROUP HOUSING COLONY AREA MEASURING 25.087 ACRES (LICENCE NO. 123 OF 2012 DATED 20-12-2012 IN SECTOR-63, GURGAON BEING DEVELOPED BY ARLIE BUILDERS & DEVELOPERS PVT. LTD. AND OTHERS IN COLLABORATION WITH DLF HOME DEVELOPERS LTD(EARLIER KNOWN AS DLF NEW GURGAON HOME DEVELOPERS PVT.LTD)

ARCHITECTURE:
ARCOP
ARCOP ASSOCIATES PVT LTD
Plot No. 36B, Sector-32, Intitutional Area,
Gurugram. Haryana. 122001. India
Tel.: 91-124-4595500
91-124-4595550
Fax: 91-124-4595550

TO BE READ WITH THIS OFFICE MEMO NO. Jan 97 DATED: 20-01-2023

ATP(HQ) STP(HQ) SE(HQ) Member Secretary BPAC BPAC BPAC

ATP(HQ)

Ram Avtar Pasial JD(HQ) JD. MEMBER BPAC

Building plans have been checked and found in order as per Public Health Services point of view.

EE(HQ) SDO(HQ) AE(HQ) GMDA GMDA GMDA

EE(HQ) Member Secretary GMDA

ARCHITECT'S SEAL & SIGNATURE

PRATEEK BHATNAGAR
ARCHITECT
M.C.A., A.I.I.A.
Registration No.: CA/2003/32077

OWNER'S SEAL & SIGNATURE

DLF Home Developers Limited
Authorised Signatory

JAN.-2023. Scale : 1:200

Drawing Title:- BASEMENT-01(PART-2)

Drawing No:- BS-02