ARC AREA

GREEN AREA CALCULATION

GROSS – D

g20	3.14	x	143.925	x	143.925	x	17.39	\	360	-	0.5	x	143.925	-	1.790	x	43.480	=	51.031	sqm.
g23	3.14	x	6.835	x	6.835	x	45	\	360	-	0.5	x	6.835	-	0.530	x	5.265	=	1.739	sqm.
g24	3.14	x	23.215	x	23.215	x	45	\	360	-	0.5	x	23.215	-	2.950	x	22.870	=	42.995	sqm.
g29	3.14	x	4.915	x	4.915	x	49	\	360	-	0.5	x	4.915	-	0.450	x	4.110	=	1.149	sqm.
g35	3.14	x	14.475	x	14.475	x	25	\	360	-	0.5	x	14.475	-	0.335	x	6.180	=	1.996	sqm.
g62	3.14	x	21.065	x	21.065	x	59	\	360	-	0.5	x	21.065	-	2.700	x	20.630	=	38.916	sqm.
g63	3.14	x	107.025	x	107.025	x	20	\	360	-	0.5	x	107.025	-	1.690	x	37.885	=	2.840	sqm.
g72	3.14	x	5.700	x	5.700	x	79	\	360	-	0.5	x	5.700	-	1.315	x	7.250	=	6.404	sqm.
g54a	3.14	x	2.535	x	2.535	x	83	\	360	-	0.5	x	2.535	-	0.900	x	3.935	=	1.435	sqm.
g54	3.14	x	2.520	x	2.520	x	88	\	360	-	0.5	x	2.520	-	0.715	x	3.500	=	1.716	sqm.
g104	3.14	x	0.500	x	0.500	x	125	\	360	-	0.5	x	0.500	-	0.270	x	0.940	=	0.164	sqm.
g110	3.14	x	1.250	x	1.250	x	176	\	360	-	0.5	x	1.250	-	1.250	x	2.500	=	2.399	sqm.
g112	3.14	x	1.250	x	1.250	x	180	\	360	-	0.5	x	1.250	-	1.250	x	2.500	=	2.453	sqm.
g127	3.14	x	5.700	x	5.700	x	90	\	360	-	0.5	x	5.700	-	1.675	x	8.070	=	9.264	sqm.
g132	3.14	x	2.500	x	2.500	x	107	\	360	-	0.5	x	2.500	-	1.015	x	4.020	=	2.648	sqm.
g134	3.14	x	6.005	x	6.005	x	52	\	360	-	0.5	x	6.005	-	0.605	x	5.270	=	2.126	sqm.
g136	3.14	x	3.005	x	3.005	x	93	\	360	-	0.5	x	3.005	-	0.940	x	4.370	=	2.813	sqm.
g140a	3.14	x	22.180	x	22.180	x	84.2	\	360	-	0.5	x	22.180	-	5.725	x	29.725	=	116.733	sqm.
g145	3.14	x	3.500	x	3.500	x	123	\	360	-	0.5	x	3.500	-	1.840	x	8.160	=	8.029	sqm.
g145	3.14	x	3.500	x	3.500	x	96	\	360	-	0.5	x	3.500	-	1.150	x	5.185	=	4.165	sqm.
g157	3.14	x	6.000	x	6.000	x	40	\	360	-	0.5	x	6.000	-	0.370	x	4.145	=	0.892	sqm.
g158	3.14	x	6.000	x	6.000	x	90	\	360	-	0.5	x	6.000	-	1.745	x	8.485	=	10.208	sqm.
																	TOTAL	=	312.314	SQM

GREEN AREA CALCULATION

GROSS – A

g1	=	1	X			16.895					X	5.790	=	97.822	SQM
g2	=	0.5	x	29.570	+	38.360					X	9.960	=	338.291	SQM
g3	=	1	X			4.143					X	5.830	=	24.165	SQM
g4	=	0.5	X	38.360	+	45.800					X	6.700	=	281.936	SQM
g5	=	0.5	X	45.800	+	45.600					X	5.500	=	159.950	SQM
g6	=	1	x			4.143					X	5.830	=	24.165	SQM
g7	=	0.5	X	45.660	+	40.045					X	8.275	=	354.604	SQM
g8	=	0.5	X	44.180	+	40.290					X	5.745	=	242.869	SQM
g9	=	0.5	X			13.960					X	5.745	=	40.100	SQM
g118	=	0.5	X	6.835	+	9.325					X	5.745	=	90.833	SQM
g33	=	0.5	X	5.565	+	5.975					X	2.640	=	15.233	SQM
g34	=	0.5	X	5.975	+	4.825					X	5.245	=	31.959	SQM
g36	=	0.5	X	4.625	+	4.615					X	14.390	=	66.482	SQM
g37	=	0.5	X	4.190	+	4.985					X	22.155	=	101.774	SQM
g51	=	1	X			16.865					X	5.445	=	91.830	SQM
g51a	=	1	X			14.700					X	8.035	=	118.115	SQM
g52	=	1	X			13.355					X	6.000	=	80.130	SQM
g53	=	1	X			16.965					X	5.445	=	92.376	SQM
g54	=	0.5	X	14.610	+	3.935					X	12.995	=	120.496	SQM
g55	=	1	X			26.220					X	12.995	=	170.689	SQM
g56	=	0.5	X	27.285	+	10.205					X	8.580	=	160.833	SQM
g57	=	0.5	X			12.585					X	4.430	=	27.879	SQM
g58	=	0.5	X			21.410					X	3.615	=	38.699	SQM
g76	=	0.5	X			3.220					X	7.515	=	12.099	SQM
g77	=	0.5	X	6.560	+	6.775					X	3.870	=	23.868	SQM
g78	=	0.5	X	14.935	+	10.910					X	22.200	=	282.440	SQM
g79	=	0.5	X	21.290	+	19.785					X	2.000	=	141.075	SQM
g80	=	0.5	X	58.050	+	60.135					X	2.065	=	123.208	SQM
g81	=	0.5	X	58.225	+	58.805					X	2.000	=	117.030	SQM
g82	=	1	X			60.350					X	2.000	=	120.700	SQM
g83	=	1	X			5.550					X	2.000	=	16.700	SQM
g84	=	1	X			60.350					X	2.000	=	120.700	SQM
g85	=	1	X			61.170					X	2.000	=	122.340	SQM
g86	=	1	X			13.690					X	2.000	=	27.380	SQM
g87	=	1	X			67.000					X	2.000	=	134.000	SQM
g88	=	0.5	X	70.305	+	71.790					X	2.000	=	142.095	SQM
g90	=	0.5	X	40.285	+	41.580					X	2.000	=	81.865	SQM
g91	=	0.5	X	154.005	+	154.195					X	2.000	=	308.200	SQM
g91	=	0.5	X	72.060	+	71.800					X	2.000	=	143.660	SQM
g92	=	0.5	X	11.510	+	11.190					X	2.000	=	22.700	SQM
g93	=	0.5	X			0.315					X	1.980	=	0.312	SQM
g94	=	0.5	X	8.305	+	5.965					X	1.980	=	14.127	SQM
g95	=	0.5	X	221.225	+	223.870					X	2.000	=	444.795	SQM
g96	=	0.5	X	91.905	+	97.014					X	1.500	=	137.014	SQM
g97	=	0.5	X	8.705	+	7.580					X	1.500	=	12.214	SQM
g98	=	0.5	X	97.385	+	100.898					X	1.500	=	148.712	SQM
g99	=	0.5	X	40.060	+	38.015					X	1.500	=	58.556	SQM
g100	=	1	X			53.470					X	2.000	=	106.940	SQM
g101	=	0.5	X	1.845	+	7.575					X	50.975	=	240.092	SQM
g102	=	0.5	X	6.885	+	7.575					X	2.495	=	18.039	SQM
g109	=	1	X			18.070					X	8.345	=	114.654	SQM
g109a	=	1	X			2.200					X	50.525	=	111.155	SQM
g111	=	1	X			2.560					X	7.490	=	18.725	SQM
g113	=	1	X			21.535					X	8.590	=	141.916	SQM
g114	=	1	X			24.555					X	23.215	=	570.044	SQM
g115	=	0.5	X	0.940	+	4.495					X	8.200	=	22.284	SQM
g116	=	0.5	X	8.485	+	11.890					X	6.000	=	60.055	SQM
g122	=	0.5	X			10.355					X	20.470	=	104.960	SQM
g166	=	1	X			17.545					X	2.105	=	36.932	SQM
g166a	=	1	X			10.295					X	7.265	=	74.793	SQM
g167	=	1	X			120.750					X	2.000	=	241.500	SQM
g169	=	1	X			115.945					X	2.000	=	231.890	SQM
g170	=	1	X			41.900					X	2.000	=	83.800	SQM
g171	=	1	X			60.350					X	2.000	=	120.700	SQM
g172	=	1	X			265.640					X	2.000	=	531.280	SQM
g173	=	1	X			55.730					X	2.000	=	111.500	SQM
g174	=	0.5	X	67.060	+	69.060					X	2.000	=	136.120	SQM
g175	=	0.5	X	53.690	+	51.890					X	2.000	=	105.380	SQM
g176	=	0.5	X			1.470					X	2.000	=	1.470	SQM
												TOTAL	=	8661.966	SQM

TOTAL GREEN AREA	=	GROSS – A	+	GROSS – B	+	GROSS – C	+	GROSS – D	+	GROSS – E	-	GROSS – 1
	=	8661.966	+	4024.092	+	3644.323	+	312.314	+	559.613	-	116.626
	=					17282.387						
TOTAL GREEN AREA	=											

GROSS – 2	+	GROSS – 3	+	GROSS – 4								
274.875	+	720.928	+	733.807								
1647.136												
15305.171												

GREEN AREA CALCULATION

GROSS – B

NO.	A		B		C			s	AREA OF = S(5-A)(5-B)(5-C)	Area	
g10	54.25	+	46.84	+	17.085	/	2	=	59.088	147041.249	383.460 SQM
g11	46.84	+	30.07	+	35.950	/	2	=	56.41	205499.403	535.907 SQM
g12	35.91	+	35.61	+	2.785	/	2	=	37.153	2447.133	49.469 SQM
g13	35.61	+	34.21	+	4.535	/	2	=	37.178	5644.973	75.133 SQM
g14	34.21	+	28.95	+	11.250	/	2	=	37.205	23874.608	154.514 SQM
g15	28.95	+	26.565	+	3.135	/	2	=	29.325	794.903	28.194 SQM
g16	13.765	+	6.79	+	30.450	/	2	=	25.523	1138.890	34.025 SQM
g17	30.49	+	7.325	+	8.960	/	2	=	13.368	1041.198	32.268 SQM
g18	43.48	+	30.305	+	27.295	/	2	=	50.49	166030.113	408.081 SQM
g21	27.295	+	39.815	+	24.605	/	2	=	45.658	110180.861	331.935 SQM
g22	39.415	+	22.67	+	17.630	/	2	=	39.858	6737.593	82.085 SQM
g25	13.91	+	11.67	+	7.295	/	2	=	17.538	2308.002	48.042 SQM
g26	16.79	+	11.91	+	8.230	/	2	=	19.465	3249.641	57.006 SQM
g27	16.79	+	16.23	+	2.560	/	2	=	17.79	421.669	20.535 SQM
g28	8.328	+	14.624	+	11.949	/	2	=	17.451	3475.437	49.754 SQM
g30	13.385	+	10.075	+	4.110	/	2	=	13.785	197.921	14.068 SQM
g31	36.075	+	10.075	+	17.235	/	2	=	26.053	2936.408	54.196 SQM
g32	9.925	+	17.235	+	10.175	/	2	=	18.608	1892.759	43.506 SQM
g38	17.76	+	12.305	+	10.650	/	2	=	20.258	3962.712	62.950 SQM
g39	10.17	+	12.305	+	17.100	/	2	=	19.688	3676.260	60.632 SQM
g40	17.1	+	16.990	+	1.490	/	2	=	17.343	83.169	9.120 SQM
g41	7.74	+	11.095	+	14.240	/	2	=	16.965	2138.798	46.246 SQM
g42	13.005	+	14.24	+	14.380	/	2	=	20.813	6869.840	82.884 SQM
g43	14.38	+	11.76	+	7.675	/	2	=	16.908	2080.889	45.065 SQM
g44	15.02	+	12.24	+	8.540	/	2	=	17.9	2731.101	52.260 SQM
g45	15.02	+	12.85	+	14.100	/	2	=	21.395	7546.478	86.870 SQM
g46	14.92	+	13.235	+	2.885	/	2	=	15.52	368.847	16.397 SQM
g47	13.235	+	5.58	+	12.030	/	2	=	15.403	1114.745	33.388 SQM
g48	4.795	+	9.865	+	11.000	/	2	=	12.83	559.356	23.651 SQM
g49	13.215	+	10.940	+	11.000	/	2	=	17.58	3350.194	57.881 SQM
g50	10.945	+	10.97	+	3.405	/	2	=	12.36	311.669	17.654 SQM
g59	37.885	+	23.465	+	23.170	/	2	=	42.26	6638.997	257.560 SQM
g60	23.17	+	20.63	+	16.570	/	3	=	30.185	27546.549	165.972 SQM
g61	19.51	+	16.57	+	21.405	/	2	=	28.743	23701.277	153.952 SQM
g64	13.535	+	14.56	+	1.775	/	2	=	14.935	103.186	10.158 SQM
g65	12.145	+	13.535	+	6.090	/	2	=	15.855	1340.790	36.617 SQM
g66	14.56	+	18.465	+	11.960	/	2	=	22.493	7958.387	89.208 SQM
g67	18.465	+	6.905	+	14.040	/	2	=	19.705	3771.773	42.092 SQM
g68	13.13	+	15.29	+	3.545	/	2	=	16.013	407.109	20.177 SQM
g69	15.29	+	15.727	+	13.935	/	2	=	22.498	9340.566	96.647 SQM
g70	15.727	+	11.360	+	13.565	/	2	=	18.65	3080.067	55.046 SQM
g71	12.13	+	13.39	+	5.635	/	3	=	15.478	1166.509	34.154 SQM
g73	7.29	+	14.68	+	8.320	/	2	=	15.145	377.547	19.431 SQM
g74	14.68	+	9.85	+	6.050	/	2	=	15.29	468.822	21.652 SQM
g75	6.61	+	9.455	+	8.180	/	2	=	11.603	631.922	25.138 SQM
									TOTAL	=	4024.092 SQM

GREEN AREA CALCULATION

GROSS – C

NO.	A		B		C			s	AREA OF = S(5-A)(5-B)(5-C)	Area	
g103	35.145	+	8.485	+	9.340	/	2	=	16.485	1262.699	35.534 SQM
g105	15.145	+	24.89	+	22.975	/	2	=	31.505	29083.165	170.538 SQM
g106a	24.89	+	25.705	+	1.530	/	2	=	26.063	268.007	16.371 SQM
g106	25.705	+	28.075	+	7.360	/	2	=	30.57	8632.896	92.803 SQM
g107	28.075	+	33.07	+	6.500	/	2	=	33.823	3996.793	63.220 SQM
g108	33.07	+	32.455	+	6.345	/	2	=	35.935	10601.480	103.963 SQM
g109	2.12	+	27.238	+	28.149	/	2	=	28.744	694.015	26.344 SQM
g117	34.625	+	39.98	+	4.050	/	2	=	44.548	56300.420	241.455 SQM
g118	21.005	+	14.775	+	14.415	/	2	=	25.098	11326.030	106.424 SQM
g119	25.565	+	35.73	+	18.540	/	2	=	39.918	51286.448	226.465 SQM
g120	35.73	+	26.8	+	18.405	/	2	=	40.445	57805.150	240.427 SQM
g123	20.47	+	12.12	+	20.505	/	2	=	26.548	14065.538	118.598 SQM
g124	12.12	+	10.64	+	7.670	/	2	=	15.215	1625.485	40.317 SQM
g128	8.07	+	13.175	+	6.175	/	2	=	13.71	311.712	17.655 SQM
g129	13.79	+	13.175	+	14.530	/	2	=	14.768	40.276	7.764 SQM
g130	14.995	+	24.47	+	14.530	/	2	=	27.018	10299.977	101.489 SQM
g131	24.47	+	23.56	+	1.720	/	2	=	24.875	306.753	17.514 SQM
g133	16.94	+	21.8	+	5.270	/	2	=	21.602	1625.360	40.314 SQM
g135	21.8	+	20.29	+	4.370	/	2	=	23.73	1841.935	42.918 SQM
g137	20.29	+	15.67	+	11.375	/	2	=	24.168	9380.334	96.904 SQM
g138	32.35	+	15.67	+	21.840	/	2	=	34.93	22720.308	150.733 SQM
g139	32.35	+	32.35	+	4.600	/	2	=	32.763	1401.362	37.434 SQM
g140	50.9	+	29.725	+	29.155	/	2	=	54.89	141436.248	376.012 SQM
g141	27.19	+	29.59	+	50.900	/	2	=	53.84	102796.633	319.838 SQM
g142	28.78	+	29.59	+	5.185	/	2	=	31.778	5540.974	74.439 SQM
g143	27.855	+	28.78	+	18.590	/	2	=	37.613	61662.624	248.320 SQM
g144	6.61	+	18.59	+	14.865	/	2	=	25.033	2004.310	44.770 SQM
g147	4.92	+	12.12	+	13.030	/	2	=	15.035	888.837	29.813 SQM
g148	13.08	+	15.08	+	3.715	/	2	=	15.913	465.761	21.581 SQM
g149	14.325	+	15.315	+	15.080	/	2	=	23.36	9214.464	95.992 SQM
g150	15.315	+	12.25	+	6.940	/	2	=	17.253	1724.427	41.526 SQM
g151	11.79	+	11.895	+	20.905	/	2	=	22.295	3385.725	58.187 SQM
g152	7.68	+	20.905	+	18.310	/	2	=	23.448	4829.167	69.492 SQM
g153	18.31	+	14.36	+	7.485	/	2	=	20.078	2554.976	50.547 SQM
g154	3.455	+	9.795	+	10.725	/	2	=	10.968	29.789	5.458 SQM
g155	7.625	+	9.795	+	6.150	/	2	=	11.785	549.756	23.447 SQM
g156	6.795	+	6.15	+	9.395	/	2	=	11.055	436.585	20.895 SQM
g158	4.145	+	9.165	+	11.675	/	2	=	12.493	283.669	16.842 SQM
g159	11.58	+	10.125	+	2.135	/	2	=	11.92	73.184	8.437 SQM
g160	10.125	+	16.165	+	9.865	/	2	=	18.078	2257.974	47.518 SQM
g161	11.25	+	9.865	+	1.970	/	2	=	11.543	54.214	7.363 SQM
g162	5.905	+	12.155	+	10.705	/	2	=	14.381	998.786	31.604 SQM
g163	2.43	+	10.39	+	10.705	/	2	=	11.763	159.327	12.622 SQM
g164	8.58	+	10	+	10.390	/	2	=	14.475	1565.159	39.562 SQM
g165	10	+	6.92	+	7.185	/	2	=	12.053	618.010	24.860 SQM
g177	1.645	+	1.47	+	2.480	/	2	=	2.705	1.359	1.166 SQM
									TOTAL	=	3644.323 SQM

DEDUCTION

GROSS –1

f	=	2	X	5.000	X	4.995	=	49.950	SQM
i	=	1	X	7.400	X	3.200	=	23.680	SQM
j	=	1	X	3.000	X	3.000	=	9.000	SQM
g1	=	1	X	5.606	X	6.000	=	33.996	SQM
						TOTAL	=	116.626	SQM

DEDUCTION

GROSS –2

NO.	A		B		C			s	AREA OF = S(5-A)(5-B)(5-C)	Area	
g	5.535	+	3.54	+	4.995	/	2	=	6.035	39.149	6.257 SQM
h	5.535	+	3.54	+	4.995	/	2	=	6.035	39.149	6.257 SQM
r	5.535	+	3.54	+	4.995	/	2	=	6.035	39.149	6.257 SQM
t	5.535	+	3.54	+	4.995	/	2	=	6.035	39.149	6.257 SQM
m	10.255	+	17.71	+	20.470	/	2	=	24.218	8246.095	90.808 SQM
m1	20.47	+	12.12	+	20.505	/	2	=	26.548	14065.538	118.598 SQM
m2	12.12	+	10.64	+	7.670	/	2	=	15.215	1625.485	40.317 SQM
a2	2.639	+	4.000	+	1.907	/	2	=	4.273	4.510	2.124 SQM
									TOTAL	=	276.875 SQM

ARC AREA

DEDUCTION

GROSS – 3

a	3.14	x	142.195	x	142.195	x	25	\	360	-	0.5	x	142.195	-	3.265	x	60.595	=	199.725	sqm.
b	3.14	x	138.630	x	138.630	x	23	\	360	-	0.5	x	138.630	-	3.180	x	59.055	=	191.152	sqm.
c	3.14	x	15.130	x	15.130	x	77	\	360	-	0.5	x	15.130	-	0.275	x	18.800	=	42.306	sqm.
d	3.14	x	14.000	x	14.000	x	45	\	360	-	0.5	x	14.000	-	1.050	x	10.650	=	7.971	sqm.
e	3.14	x	23.400	x	23.400	x	23	\	360	-	0.5	x	23.400	-	0.350	x	8.415	=	12.960	sqm.
k	3.14	x	14.310	x	14.310	x	144	\	360	-	0.5	x	14.310	-	9.850	x	27.190	=	196.565	sqm.
m	3.14	x	35.000	x	35.000	x	34	\	360	-	0.5	x	35.000	-	1.535	x	20.505	=	20.181	sqm.
n	3.14	x	9.525	x	9.525	x	40	\	360	-	0.5	x	9.525	-	0.570	x	8.500	=	2.949	sqm.
q	3.14	x	14.875	x	14.875	x	79	\	360	-	0.5	x	14.875	-	3.435	x	19.010	=	43.727	sqm.
a3	3.14	x	1.500	x	1.500	x	123	\	360	-	0.5	x	1.500	-	2.639	x	0.789	=	2.957	sqm.
																TOTAL	=	720.628	SQM

DEDUCTION

GROSS –4

1a	=	1	X	6.120	X	7.200	=	44.064	SQM
1b	=	1	X	7.400	X	3.200	=	23.680	SQM
1c	=	1	X	16.805	X	3.710	=	28.737	SQM
1d	=	1	X	2.400	X	3.400	=	8.160	SQM
1e	=	1	X	1.490	X	3.200	=	4.768	SQM
1f	=	1	X	2.410	X	5.630	=	13.568	SQM
1g	=	1	X	3.500	X	3.200	=	11.200	SQM
1h	=	1	X	8.160	X	1.700	=	13.872	SQM
1i	=	1	X	8.495	X	1.710	=	14.528	SQM
1j	=	1	X	7.400	X	3.200	=	23.680	SQM
1k	=	1	X	5.240	X	1.570	=	8.227	SQM
1l	=	1	X	6.000	X	1.500	=	9.000	SQM
1m	=	1	X	6.000	X	1.500	=	9.000	SQM
1n	=	1	X	4.900	X	1.500	=	7.350	SQM
1o	=	1	X	6.410	X	1.500	=	9.615	SQM
1q	=	1	X	7.400	X	3.200	=	23.680	SQM
1r	=	1	X	5.190	X	2.425	=	12.586	SQM
1s	=	1	X	3.200	X	7.400	=	23.680	SQM
1t	=	1	X	8.545	X	13.930	=	119.032	SQM
1u	=	1	X	16.185	X	1.140	=	18.451	SQM
1v	=	1	X	90.092	X	2.000	=	180.184	SQM
1w	=	1	X	63.270	X	2.000	=	126.540	SQM
						TOTAL	=	733.607	SQM

Note :–

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVENT IS CODES FOR EARTH QUAKE RESISTANCE.
2. THE BUILDING IS ARTIFICALLY LIT AND MECHANICALLY VENTILATED.

TO BE READ WITH THIS OFFICE MEMO NO. 2097
DATED: 20-01-2023

ATP(HQ) STP(HQ) SVP(HQ) CE(HQ)
Member Secretary Member Chairman
BPAC BPAC BPAC BPAC

ATP(HQ) Ranjivatar Bas JD/PT
MEMBER BPAC
JD. A.T.P

LEGEND:–

PROJECT :

REVISED BUILDING PLANS OF GROUP HOUSING COLONY AREA MEASURING 25.087 ACRES (LICENCE NO. 123 OF 2012 DATED 20-12-2012 IN SECTOR-63, GURGAON BEING DEVELOPED BY ARLIE BUILDERS & DEVELOPERS PVT. LTD. AND OTHERS IN COLLABORATION WITH DLF HOME DEVELOPERS LTD(EARLIER KNOWN AS DLF NEW GURGAON HOME DEVELOPERS PVT.LTD)

ARCHITECTURE:

ARCOP

ARCOP ASSOCIATES PVT LTD
Plot No. 36B, Sector-32, Intitutional Area,
Gurugram. Haryana. 122001. India
Tel.: 91-124-4595500
91-124-4595550
Fax: 91-124-4595550

ARCHITECT'S SEAL & SIGNATURE	OWNER'S SEAL & SIGNATURE
PRATEEK PHANDHAIR 01/2023 32072	

JAN.–2023. | Scale : 1:600

Drawing Title:– GREEN AREA CALCULATION PHASE-1 & PHASE-2

Drawing No:– ST-03